

NATURAL RESOURCES CONSERVATION SERVICE CONSTRUCTION SPECIFICATION

REINFORCED CONCRETE BLOCK CONSTRUCTION

1. SCOPE

Construction work covered by this specification shall not be performed between November 1 and the following April 15 unless the site conditions and/or the construction methods to be used have been reviewed and approved in writing by the NRCS Engineer or designated representative.

All specifications for reinforced concrete installation except those dealing with "Concrete Forms" and "Form Removal and Concrete Repair" shall be followed for reinforced concrete work in reinforced concrete block construction.

The low forms required for the base for reinforced concrete block construction may be relatively simple in nature. However, they must be stacked or braced sufficiently that the required dimensions for the base are obtained.

Forms higher than 12 inches - example one side of a footing - should be braced on approximately 24 inch centers in both directions. Such forms for footings must be removed before backfilling

2. MATERIALS

a. Concrete blocks shall be new, hollow, load-bearing type units. They shall be dense and strong. Where the quality of a manufacturer's blocks has not been determined by laboratory tests, it may be evaluated by the following field tests:

- (1) Break - with heavy hammer - through several parts of the block and observe the nature of the break in each instance. If the break goes through an appreciable number (say 20 percent) of the coarse aggregates, this is evidence of a strong block. If goes around almost all of the coarse aggregate, this indicates a weak block.
- (2) If the block has very little coarse aggregates in it, this also indicates a weak block.

Concrete blocks which have been tested and found to meet the requirements of ASTM C90 grade "N", type "I" will comply with this specification.

b. Prefabricated wire reinforcement for embedment in horizontal mortar joints shall consist of two or more longitudinal wires that are connected by welded cross wires. The distance between weld contacts of cross wires with each longitudinal wire shall not exceed 8 inches for smooth wire nor 16 inches for deformed wire.

c. Mortar for concrete block work shall conform to the following:

- (1) Water shall be clean and free of injurious amounts of oil, salt, acid, alkali, organic matter or other deleterious substances.
- (2) Aggregate (sand) for mortar shall be graded so that 100 percent will pass a #4 sieve (0.019 inch), no more than 5 percent will pass a #100 sieve and no more than 1 percent will pass a #200 sieve. It shall not contain more than 1 percent of silt or clay. Sand which meets ASTM C144 will meet this criteria.
- (3) Proportions of mortar shall be as shown on the drawings.

Mixing water in adequate quantity to produce workability. This will usually be about 6 gallons for each bag of portland cement or masonry cement but may be more or less depending upon the moisture of the sand.

(4) Once mortar has been mixed, it shall be used within 2-1/2 hours. Older mortar should be discarded.

(5) All mechanically mixed mortar shall be mixed a minimum of 5 minutes after all materials have been added. Hand mixed mortar shall be mixed at least 10 minutes and in small batches of 2 cubic feet or less.

d. Concrete for Block Core Fill (Grout) shall conform to the following:

(1) Water shall be clean and free of injurious amounts of oil, salt, acid, alkali, organic matter or other deleterious substances.

(2) Grout for filling the blocks shall be a 3000 psi concrete mix.

3. BLOCKS - LAYING AND FILLING WITH GROUT

No more than 4 courses of concrete blocks (called a lift) may be laid without setting the reinforcing steel and filling the cores with grout.

The grout fill of each lift shall be terminated at approximately 4 inches below the top of the top course of blocks to provide a construction joint.

Reinforcing bars shall extend at least 30 bar diameters above the top of each lift (except the finish lift). All bars shall end at least 1-1/2 inches below the top of the grout fill of the top lift.

The cores of all concrete blocks shall be well wetted before grout fill is placed in them (however there shall not be appreciable water standing on top of the previous grout pour).

The grout fill in each concrete block core shall be well tamped throughout its depth after the reinforcing steel is in place.

Tamping may be accomplished using a 48-inch length of reinforcing bar or a 1 inch x 1 inch wood strip.

4. BACKFILLING CONCRETE BLOCK WALLS

The backfilling of new concrete block walls shall be controlled by the same precautions as those for new concrete walls.

5. ADDITIONAL ITEMS WHICH APPLY TO THIS JOB