

**NATURAL RESOURCES CONSERVATION SERVICE
CONSTRUCTION SPECIFICATION**

STRUCTURE REMOVAL

1. SCOPE

The work shall consist of the removal, salvage and disposal of structures (including fences) shown on the drawings or structures that must be removed to perform other items of work.

2. MARKING

Each structure unit to be removed will be marked by the NRCS Engineer or designated representative.

3. SALVAGE

Structures that are designated to be salvaged shall be carefully removed and neatly placed in the specified storage areas. Salvaged structures that are capable of being disassembled shall be dismantled into individual members or sections. Such structures shall be neatly matchmarked with paint prior to disassembly. All pins, nuts, bolts, washers, plates and other loose parts shall be marked or tagged to indicate their proper locations in the structure and shall be fastened to the appropriate structural member or packed in suitable containers. Materials from fences designated to be salvaged shall be placed outside the work area on the property from which they were removed. Wire shall be rolled into uniform rolls of convenient size. Posts and rails shall be neatly piled.

4. DISPOSAL OF REFUSE MATERIALS

Unless otherwise specified, refuse materials resulting from structure removal shall be burned or buried at locations approved by the NRCS Engineer or designated representative or otherwise disposed of as specified or approved.

5. ADDITIONAL ITEMS WHICH APPLY TO THIS JOB